# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT18377/CALL-2

## APPROVED SCHEDULE - B

**EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016**

**Construction of cement concrete Balance roads at Thindlu and surrounding area in ward No 09 in vidyaranyapura sub Division.**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of JAYAPRAKASH T | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 1 | 135.3 | Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work | Cum | 83.15 | 11250.20 | Rupees Eighty Three and Fifteen Paise Only |
| 2 | 787.5 | Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200 m (within average thickness of 15 cms) etc complete as per specifications and directions of engineer in charge of the work | sqm | 55.08 | 43375.50 | Rupees Fifty Five and Eight Paise Only |
| 3 | 177.68 | Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 5070.6 | 900944.21 | Rupees Five Thousand Seventy and Sixty Paise Only |
| 4 | 139.06 | Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams etc complete as per specifications and directions of engineer in charge of the work | Cum | 6332.04 | 880533.48 | Rupees Six Thousand Three Hundred Thirty Two and Four Paise Only |
| 5 | 1184.5 | Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc complete as per specifications and directions of engineer in charge of the work | Sqm | 97.2 | 115133.40 | Rupees Ninety Seven and Twenty Paise Only |
| 6 | 113.5 | Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator and HOM of machinery including cost of blade coolant etc including cleaning of groove and providing sand and hot bitumne fillars, and filler metal etc., indluding cost of converyance of all materials, labours, lead and lift charges and all other incidental charges as per drawing and as per specification Concrete Pavement etc complete as per specifications and directions of engineer in charge of the work | Rmt | 124.2 | 14096.70 | Rupees One Hundred Twenty Four and Twenty Paise Only |
| 7 | 135.3 | Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 11.90 Km etc complete as per specifications and directions of engineer in charge of the work | Cum | 106.34 | 14387.80 | Rupees One Hundred Six and Thirty Four Paise Only |
| | | | | | 1979721.29 | |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

30/3/16

30/03